



# Kootenai River Habitat Restoration Program



Kootenai Tribe of Idaho - January 27, 2014  
Presentation for Kootenai Valley Resource Initiative






# Decline of native species

---

**Kootenai River  
White Sturgeon  
ENDANGERED**



**Burbot  
PETITIONED**



**West Slope  
Cutthroat  
PETITIONED**



**Bull trout  
THREATENED**



**South Arm Kokanee  
FUNCTIONALLY EXTINCT**




**Columbia River Redband Trout**

# What is the Kootenai River Habitat Restoration Program?

---

- Program consisting of multiple Kootenai River habitat restoration projects
- Projects are designed to restore and enhance aquatic habitat conditions for Kootenai River white sturgeon (and other native fish too)
- Projects work together to restore habitat in ways that are consistent with current land uses and river operations
- Addresses Libby Dam BiOp RPA



# Oversight, review & coordination

## From concept to construction

---

**Tribal Council Oversight**

**Project Management Team**

**Adaptive Management Team**

**Design Team**

**Modeling Subcommittee**

**Community**

**Policy Team**

**Co-Manager & Agency Review Team**

**Landowners**

**Peer Reviewer Advisory Team (Multi-disciplinary)**

**Elected Officials**

**Stakeholders**

**Project Implementation**

# 2011-2013

## Six KRHRP Projects on the Ground



# Major Types of Treatments Implemented 2011-2013

---

- 1. *Pool forming structures & pool creation or enhancement*** to encourage Kootenai sturgeon to migrate to upstream habitat & to provide holding habitat for sturgeon & other native fish
- 2. *In river & bank structures*** to create more diverse & complex habitats for sturgeon & other native fish
- 3. *Side channel reconnection & floodplain creation or enhancement*** to enhance the food web & provide habitat for juvenile Kootenai sturgeon & other native fish
- 4. *Riparian enhancement*** (& riparian buffer fencing) to enhance the food web & provide cover for native fish

# 2011 Project Phase 1A Pre-project conditions




**2011**

**1A Project during construction**



# 1A Project Site after construction




2012 Project

Upper Meander pre-project conditions




# 2012 Project - Upper Meander



# A sturgeon “pool ladder”

- Upper Meander project plus other projects contribute to development of a “pool ladder” to encourage upstream sturgeon migration (and habitat for other native species)








# KOOTENAI RIVER HABITAT RESTORATION PROGRAM

## POOL LADDER CONCEPT

### MAP PANEL INDEX

-  Existing Pool
-  Proposed/  
Constructed Pool




# 2012 Project Upper Meander construction



10/24/2012

# Upper Meander pile structure

Flow





# Physical Monitoring Instrumentation



**2012 Project  
North Side Channels  
pre-project conditions**



# 2012 Project North Side Channel during construction



10/24/2012

# 2012 Construction North Side Channels





# 2013 Project

## Middle Meander pre-project condition



# 2013 Project

## Middle Meander pre-project condition



An aerial photograph showing a large reservoir with a significant portion of its water drained. A large, flat, sandy area in the center of the reservoir is being worked on by several yellow excavators and bulldozers. The water is dark green and blue, with some areas appearing muddy. The surrounding landscape includes green grass, trees, and distant mountains under a clear blue sky.

**Middle Meander  
Construction of “Mega Pool”**



# Middle Meander - Construction





# Middle Meander - Construction







# Middle Meander – December 2013



# 2014 KRHRP Project


---

- **Spawning Rock enhancement at 2 sites in Meander Reach - Shorty's & Myrtle Creek**
- Biological objective - to provide rocky substrate to support sturgeon spawning & early life stage survival
- **Worked with IDFG and others to identify & refine best location**
- Construction August to November 2014



# 2015 & 2016 Projects

- Bonners Ferry Islands & Straight Reach projects
- Will be staged over 2 years (pending approval through environmental compliance & permitting processes)
- Bonneville Power Administration holding EA scoping meeting February 26, 2014



# Bonnerr's Ferry Islands Project






IMAGE: October 2011  
5,000 cfs

0 500 1,000 Feet

# Straight Reach Project

IMAGE: October 2011  
5,000 cfs



0 500 1,000 Feet

# Primary Biological Objectives


---

- Increase the number of **large deep pools** to aid/encourage sturgeon to migrate upstream to higher quality spawning habitat



- Increase the area of **vegetated floodplain surfaces** that provide food web support

- Add **rocky substrate** to support Kootenai sturgeon egg attachment & early life stage survival (Straight Reach)



- **Many additional biological benefits to other species including burbot & salmonids**




# Assessing & Addressing Technical Risk

Design performance summary identifying the ability of design scenarios to manage technical risk


Risk Element	Potential Consequence	Risk Mitigation Strategy	Risk Assessment Method	Design Performance
Flood Risk	Project increases flood elevations causing damage to structures	Coordinate with USACE water managers for model inputs and risk tolerances	Hydraulic Modeling: Evaluate project effects based on the CRT model used by USACE for assessing Libby Dam management scenarios.	Slight increase in water surface elevations from project.  Refine design to comply with regulations
Sediment transport	Project causes deposition or scour resulting in channel instability	Coordinate with Modeling Subgroup and PRAT advisors to establish modeling scenarios and review results	Evaluate morphologic changes using 2D bed evolution model	Slow morphological changes. Test threshold scenarios.  To be confirmed with bed evolution model for refined design
Bank erosion	Project increases bank erosion	Design bank treatments to withstand anticipated range of hydraulics	Evaluate project effects using 2D hydraulic model	Bank conditions improved on restored banks. Bank conditions maintained on non-restored banks.
Utilities and infrastructure	Project alters hydraulic conditions at utilities or infrastructure	Coordinate with owners to review risks and mitigation strategies	Evaluate project effects using models described above	Results demonstrate insignificant change to bridge hydraulics.

# Subsurface Conditions



Boring ID	Bed Elevation (ft)	Desired Boring Elevation (ft)	Desired Boring Depth (ft)	Water Depth at 10,000 ds (ft)	Latitude	Longitude
1	1747.80	1730	17.80	1.39	48.698044	-116.31807
2	1747.65	1730	17.65	1.66	48.698125	-116.31734
3	1748.45	1730	18.45	1.09	48.69835	-116.31679
4	1750.48	1730	20.48	0.36	48.698779	-116.30944
5	1751.98	1730	21.98	0.00	48.698542	-116.30799
6	1751.70	1730	21.70	0.00	48.698244	-116.30673
7	1750.71	1730	20.71	1.04	48.695958	-116.30225
8	1753.65	1730	23.65	0.00	48.695025	-116.30151
9	1750.84	1730	20.84	1.48	48.694781	-116.30047
10	1750.85	1730	20.85	2.95	48.695932	-116.29559
11	1748.69	1730	18.69	5.32	48.695977	-116.29416
12	1747.91	1730	17.91	6.24	48.69601	-116.2927

## KOOTENAI RIVER HABITAT RESTORATION PROJECT BONNERS FERRY ISLANDS BORING LOCATIONS



1:9,000  
1 inch = 750 feet

08.21.2013  
Imagery: Kootenai Tribe of Idaho  
Acquisition date: October 27, 2011.

# KOOTENAI RIVER HABITAT RESTORATION PROJECT

## STRAIGHT REACH

EXISTING CONDITION, 31,780 CFS (06.03.2010)

BOTTOM VELOCITY (FPS) - AT 0.5 METERS ABOVE BED



### RIVERBED GEOLOGY




- Fine - Very Coarse Generally fine to coarse gravel
- Very Fine - Coarse Generally fine to medium gravel
- Embedded 65-100% embedded

### RETRIEVED EGG MAT LOCATION

- Number of Eggs Found (2007-2013)
- 0 (not colored)
  - 6-10
  - 16-31
  - 1-5
  - 11-15



09.2013, River Design Group, Inc., Data RDO, IDPO, USGS.




# Next Steps Bonners Ferry Islands & Straight Reach Projects

---

- Continued coordination with landowners, infrastructure owners, City, County, community, BNSF, IDT, UP, etc.
- **Continued flood risk coordination and compliance**
- Support BPA in completion of EA
- **Additional modeling and feasibility analysis to refine designs**
- Complete final designs
- **Staged implementation 2015 & 2016**



Questions  
about  
KRHRP?



# Kootenai River Native Fish Conservation Aquaculture Program - Construction Update



Kootenai Tribe of Idaho - January 27, 2014  
Presentation for Kootenai Valley Resource Initiative

# Kootenai River Native Fish Conservation Aquaculture Program

---

- Includes Kootenai River white sturgeon & burbot aquaculture at the Tribal Facility & new Twin Rivers facility
- KVRI Burbot Subcommittee and Burbot Conservation Strategy




# Kootenai River Native Fish Conservation Aquaculture Program

---

- Kootenai Tribe completed the Northwest Power & Conservation Council's Three Step planning process for new & expanded hatchery projects in March 2013
- BPA issued the environmental assessment (EA) & finding of no significant impact (FONSI) May 15, 2013
- Kootenai Tribe & BPA signed a Memorandum of Understanding for the Hatchery Program in May 28, 2013
- Two general construction contractors selected (Goodfellow Brothers and BF Builders) & construction began June 1, 2013
- Completion scheduled for fall 2014





# Twin Rivers Hatchery Site




# Twin Rivers Hatchery













**STURGEON**



**BURBOT**



**Administrative / Mechanical**





08 22 2013





09 26 2013





11 07 2013





01 02 2014



# Trench for electrical – August 2013









09 05 2013

# Kootenai Intake – October 2013



# Kootenai Intake Trenching – Oct 2013



# Kootenai Intake Trenching – Oct 2013



# Kootenai Intake Screens— Oct 2013



# Kootenai Intake Piping – Dec 2013





# Moyie Pump Station –Dec 2013



# Moyie Water Intake – Dec 2013



# Questions about the Hatchery?



The Kootenai Tribe wishes to thank the many partners and friends who helped with planning, coordination, design, permitting, funding and construction of the KRHRP projects and the Hatchery Upgrades and Construction.

The Tribe also wishes to thank the individual landowners who made it possible to access the project sites and who allowed work to occur on their properties or helped provide materials.

And KVRI and the community of Bonners Ferry!

Without all of you – none of this would have been possible.

Thank you all !!!

# Burbot MOU Expires in 2015

