

Kootenai Water Main Loop Construction, Addendum No. 1

What type of hydrant is acceptable for the project?

- American Flow Control, AKA American Darling Model B-62-B5 or approved equal.

Does bedding material need to be brought in for the project?

- Per the tribal utility, there is the potential to encounter large rocks (6-12 inches). Bedding material may be needed for the project.